



## TEST SITE : INSTALLATION TIPS

**DATE** : 04 July 2014  
**VENUE** : Utility Systems Head Office  
**AUTHOR** : Marcus Lee Thulsidas

Water Management Device – WMD

User Interface Unit – UIU

Radio Frequency – RF

Installation Check List for Prepayment

1. Verify documentation is correct for installation
2. Ensure relevant installation tools and fittings are available
3. Ensure meter is registered with Vendor
4. Ensure water management device (WMD) has an allocated UIU
5. Ensure UIU is paired to WMD
6. Ensure UIU # commands are set
7. Vend a test credit token to the minimum required unit and test it
8. Ensure when installing the direction of flow of water is correct
9. Test UIU RF range once the WMD has been installed
10. Inform customer of UIU features and listed instructions on the reverse side of UIU